

OFFICE OF THE DY. GENERAL MANAGER UNIT 2ND.

Office Complex First Floor, Rail Head, Panama Chowk, Jammu.


Tele Nos. 2471440, 2471428, 2471423.



Annexure-"A"

Name of work: SUPPLY OF ROPES/ SUSPENDERS AND WIND SLING FOR LAUNCHING OF 260 MTR. SPAN FOOT SUSPENSION BRIDGE OVER RIVER TAWI AT KATAL BATAL (PAHER DEVTA JI) DANSAL BLOCK DISTRICT JAMMU

S. No	Particulars	Unit	App. Qty.	Rate to be quoted
1)	Supply of			
a)	Main Cable Size : 48mm Construction : 7 x 37 prestretched Lay : RHO Coating : Fully Galvanized Tensile : 1570 N/MM ² IS : IS 9282/2002	Mtr.	10 x 430 (length)	
b)	Wind Cable Size : 40mm Construction : 7 x 37 prestretched Lay : RHO Coating : Fully Galvanized Tensile : 1570 N/MM ² IS : IS 9282/2002	Mtr.	4 x 350 (length)	
c)	Main & wind suspenders Size : 12 mm Construction : 7 x 7 prestretched Lay : RHO Coating : Fully Galvanized Tensile : 1570 N/MM ² IS : IS 9282/2002	Mtr.	1 x 2370 1 x 630 (length)	


Deputy General Manager,
JKPCC Ltd., Unit 2nd,
Jammu.